BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work:Improvements to roads and drains at 2nd main & 8th cross Manjunatha Nagara in Ward no 14 (Bagalagunte)

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in **Ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	843.86	86.92	Rupees Eighty six & Ninty Two Paise Only
2	Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	45.60	5159.02	Rupees Five Thousand One hundred Fifty Nine & Two Paise Only
3	Providing and removing **centering,** shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications,	Sqm	1094.40	310.58	Rupees Three hundred ten & Fifty Eight Only
4	Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008- i) Upto 5 m height.	Cum	114.00	6965.26	Rupees Six thousand nine hundred Sixty Five & Twenty Six Only
5	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specifications	Tonne	7.91	66482.14	Rupees Sixty Six thousand four hundred Eighty two & Fourteen Only
6	Supplying and fixing **precast** rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	228.00	1698.00	Rupees One thousand Six hundred Ninty Eight Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION

Signature of the Contractor

Executive Engineer

Scanned by CamScanner

	I material construction of granular sub-providing coarse graded crushed stone of Granite/ trap/basalt material spreading layers with motir grader on prepared mixing by a mix in place method with at OMC, and Compacting with vibratory achieve the desired density, complete as per tions.by mix in a Place method for course Granular Sub Base Material as per 400-2 for I material	Cum	240.12	1518.98	Rupees One Thousand Five hundred & Eighteen & Ninty Eight Paise Only
	ng, laying, spreading and compacting graded aggregates to **wet mix macadam** specifications ing pre mixing the material with water at OMC in anical mix plant carriage of mixed method of to site, laying in uniform layers with paver in sub / base course on well prepared surface and pacting with vibratory roller to achieve the desired sity complete as per specifications. Specification 406 with all leads and lifts etc., complete as per direction of Engineer-in-charge of the work.	Cum.	480.24	1768.08	Rupees One thousand Seven hundred Sixty Eighy & Eight Paise Only
	oviding and applying primer coat with S.S. Bitumen mulsion on prepared surface of granular base such WBM, WMM including clearing of road surface and praying primer at the rate of 0.6 kg / sqm using echanical means complete as per specifications, ith all leads and lifts etc., complete as per the irection of Engineer-in-charge of the work	Sqm	2401.20	27.56	Rupees Twenty Seven & Fifty Six Paise Only
	Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications.		2401.20	11.66	Rupees Eleven & Sixty Six Paise Only
11	Providing and laying bituminous concrete with hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder and filter transporting the hot mix to work site laying with paver finisher to the required grade, level and alignment. rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH Speicification clause no 500.9 complete in all respects complete as per specification no 509. using 40/60 TPH Capacity H.M.P With Mechanical paver Gr-II (30 mm to 45 mm) with 6% VG-30 Bitumen (p-165, lt 21.22.6) PWD SR 2016-17	Cum	108.05	7083.98	Rupees Five Thousand One hundred Twenty Nine & Thirty Four Paise Only
12	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	843.86	85.65	Rupees Eighty Five & Sixty Five paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Scanned by CamScanner